



Blazing Design, Inc.  
P.O. Box 164  
Essex Junction, VT 05453

# Estimate

Date	Estimate #
4/1/2016	10664

Name / Address
Ean Briere

Project	Terms
	See estimate

Item	Qty	Description	Cost	Total
		Supply, install and start up a propane gas insert to be installed in an existing factory built fireplace that is 35" wide x 22 1/2" high x 18" deep		
Shop Materials		American Hearth DV33IN-33LP - Medium Franklin	1,829.00	1,829.00T
Shop Materials		DVFTQ-33-TBL - Safety Screen (required)	185.00	185.00T
Shop Materials		S33-3-BL - 3 Piece surround with 3" sides and 6' top. Other options available	107.00	107.00T
Shop Materials		C33-3-BL -Surround bottom cover	63.00	63.00T
Shop Materials		Custom cut plate to go over existing fireplace	250.00	250.00T
Shop Materials		46DVA-CL33 Vent kit - includes 2 - 3" liners, chimney cap	340.00	340.00T
Shop Materials		gas piping	150.00	150.00T
Shop Materials		miscellaneous caulk, vent sealant, cleaning supplies	35.00	35.00T
Shop Materials		Wireless Thermostat - not required, but recommended, other options available. ADD \$173 plus tax	0.00	0.00T
Field Work		Permit	85.00	85.00
Gas Insert Instal...		gas piping labor	350.00	350.00
Gas Insert Instal...		insert installation	1,000.00	1,000.00
		Note:  Electrical work is not included - FIreplace insert requires 120V to operate. A duplex outlet should be installed in the fireplace.  Clearance to combustible mantles need to be within the manufacturer's requirements as listed in the installation manual.		
<b>Subtotal</b>				\$4,394.00
<b>Sales Tax (6.0%)</b>				\$177.54

Terms: 50% due upon acceptance, 25% due upon delivery, 25% due upon completion. 4% added for credit card payments. 2% penalty added for late payments. Estimate valid for 45 days.

**Total** \$4,571.54

Phone #
(802) 316-3081